

GENERAL DESCRIPTION – A permanent area set aside for casual or competitive recreation. Sports areas have specific playing surfaces that cannot be moved without capital works.

Feature Type: Polygon

CLASSIFICATION INFORMATION

1. Ownership

See the definitions section for more details. Sports Areas that are open to the public are typically council owned while fenced off and gated areas are club owned.

2. Sports Area Surface Material

See the definitions section for a list and descriptions of the different construction material types.

3. Number of Wickets

If the sports area is a Cricket Block, how many Cricket Wickets are present on the block?

4. Level

Where applicable state the level of play the area is used for.

5. Field Court Number

Where applicable, state the number or other identifier for the area. This will apply mainly to cricket blocks, netball courts and tennis courts.

6. Sports Season

What season is this sports field used for?

- a) Non-Seasonal
- b) Summer
- c) Winter

PHOTOS



Tennis Court



Cricket Block

CLASSIFICATION INFORMATION

6. Sports Area Type

- a. **Athletics Surface** - Artificial running track. Can be circular, oval or straight for run-ups to javelin and long-jump.
- b. **Baseball** – Baseball diamond and pitchers mound.
- c. **Basketball** – Basketball court.
- d. **Basketball Half Court** – Half a basketball court.
- e. **BMX** – Engineered, unpaved track with banking and jumps designed for BMX.
- f. **Bowls** – Bowling green.
- g. **Cricket Block** – Maintained area in the centre of a cricket oval. One or more cricket wickets are marked out on the cricket block.
- h. **Croquet** – Croquet court.
- i. **Cycling** – A permanent hard surface specifically for cycling training and competitions, e.g. the velodrome.
- j. **Discus** - Concrete circle for throwing discus. 2.5m Diameter with 20mm lip.
- k. **Golf** – Golf course.
- l. **Hockey** – Artificial surface hockey field.
- m. **Long Jump** - Sand pit for jump landings.
- n. **Mini Golf** – Mini golf course.
- o. **Netball** – Netball court.
- p. **Petanque** – Loose gravel petanque court.
- q. **Shot-put** – Concrete circle for throwing shot-put. 2.135m Diameter with 100mm high lip at front.
- r. **Skateboarding** – Area with skateboarding equipment.
- s. **Softball** – Softball diamond and associated permanent surfaces.
- t. **Tennis** – Tennis court.
- u. **Volleyball** – Hard surface or sand area for volleyball or beach volleyball.

ADDITIONAL COMMENTS



Basketball Half Court

Skateboard Area



GENERAL DESCRIPTION – Assets installed to allow sports to be played or practised.

Feature Type: Point

CLASSIFICATION INFORMATION

1. Ownership

See the definitions section for more details. Sports Equipment installed in or on club owned sport or recreation areas can be assumed to be privately owned by the club. Sports equipment in public areas should be checked for labels saying it belongs to a club.

2. Sports Equipment Type

- a. **Basketball Hoop** – Hoop and backboard mounted on a sturdy pole or structure.
- b. **BMX Jump** – Mound of earth forming an obstacle on a BMX track.
- c. **BMX Ramp** – Inclined surface at the start of a BMX track with the incline falling towards the track.
- d. **BMX Start Equipment** – Fences or other barriers across a BMX Ramp to prevent bikes accessing the track early.
- e. **Cricket Net** – Tall wire mesh fencing around a cricket wicket for batting and bowling practise. A wire mesh roof over the whole or part of the length is often included.
- f. **Goal Posts** – Structure forming the goal for soccer, rugby or hockey.
- g. **Netball Hoop** – Hoop mounted on a pole. Poles can be fixed in place or moveable.
- h. **Scrum Machine** – Padded, weighty device, often sled mounted, for scrum practise.
- i. **Skateboard Bowl** – Hollow in a hard surface designed for skateboarding.
- j. **Skateboard Rail** – Strong metal handrail for skateboards to slide along/down. Rails may be steel pipes set in concrete or steel box section on poles.
- k. **Skateboard Ramp** – Ramp to form a jump for skateboards.

PHOTOS



Goal Posts



Tennis Net

CLASSIFICATION INFORMATION

- l. **Skateboard Steps** – Concrete steps installed as an obstacle for skateboards. Skateboard steps often have a skateboard rail down the middle.
- m. **Softball Net** – Tall fences behind home base on a softball diamond and extending towards 1st and 3rd bases.
- n. **Tennis Net** – Net separating a tennis court into two halves. The net is 1.1m high at each end and 0.91m high in the centre.
- o. **Tennis Practise Wall** – Solid wall adjacent the edge of a paved area. Often, but not always, will have a painted horizontal line to represent a net.
- p. **Volleyball Net** – Net separating a volleyball court into two halves. The top of the net is 2.25-2.45m high with the bottom one metre below the top.

3. Construction Material

See the definitions section for a list of construction materials with descriptions.

4. Surface Finish

See the definitions section for a list of surface finishes with descriptions.

ADDITIONAL COMMENTS



Skateboard Ramp

Skateboard Rail



GENERAL DESCRIPTION – An outdoor playing area for various sports. Sports fields are formed by line markings on sports turf. (Sports turf is the grass and is another asset).

Feature Type: Polygon

CLASSIFICATION INFORMATION

1. Sports Field Type

What sport is the field for?

- a. **American Football**
- b. **Athletics** – Includes any athletics related markings on turf e.g: running tracks or the legal sector marks for throwing events.
- c. **Aussie Rules**
- d. **Baseball Outfield**
- e. **Cricket Outfield**
- f. **Football** – Commonly known as soccer.
- g. **Gaelic Football**
- h. **Hockey**
- i. **Lacrosse**
- j. **Polo**
- k. **Rugby League**
- l. **Rugby Union**
- m. **Softball Outfield**
- n. **Touch Rugby**
- o. **Volleyball** – Volleyball court marked out on grass.

2. Level

What level of players is the field designed and sized for?

- a. **Premier** – Standard sized field for the highest level of player.
- b. **Senior** – Standard size field.
- c. **Modified** – Three quarter sized field.
- d. **Intermediate** – One half sized field.
- e. **Junior** – One quarter sized field.
- f. **Mini** – Field for 5-6 year olds. One eighth to one sixth sized field.
- g. **Recreational** – Sports field only used for informal recreational purposes. Cannot be used for matches (e.g. half fields).
- h. **Training** – Sports field only used for training. Not suitable for matches.

3. Field Court Number

What is the ID number of the field?

4. Associated Sports Association

What sports club, organisation or association is associated with the field?

5. Sports Season

What season is this sports field used for?

- d) Non-Seasonal
- e) Summer
- f) Winter