



Spreydon Domain - Equipment  
Shed and Changing Room  
Qualitative Engineering Evaluation

**Reference:** 229618  
**Prepared for:**  
Christchurch City Council

Functional Location ID: PRK\_1099\_BLDG\_008

Address: 33 Domain Terrace, Spreydon

**Revision:** 2  
**Date:** 17 October 2013

# Document Control Record

Document prepared by:

Aurecon New Zealand Limited  
 Level 2, 518 Colombo Street  
 Christchurch 8011  
 PO Box 1061  
 Christchurch 8140  
 New Zealand

**T** +64 3 375 0761  
**F** +64 3 379 6955  
**E** christchurch@aurecongroup.com  
**W** aurecongroup.com

A person using Aurecon documents or data accepts the risk of:

- Using the documents or data in electronic form without requesting and checking them for accuracy against the original hard copy version.
- Using the documents or data for any purpose not agreed to in writing by Aurecon.

Document control				aurecon		
<b>Report Title</b>		Qualitative Engineering Evaluation				
<b>Functional ID</b>		<b>PRK_1099_BLDG_008</b>	<b>Project Number</b>		229618	
<b>File Path</b>		P:\ 229618 - Spreydon Domain - Equipment Shed and Changing Room.docx				
<b>Client</b>		Christchurch City Council	<b>Client Contact</b>		Michael Sheffield	
<b>Rev</b>	<b>Date</b>	<b>Revision Details/Status</b>	<b>Prepared</b>	<b>Author</b>	<b>Verifier</b>	<b>Approver</b>
1	24 June 2013	Draft	S. McConway	S. McConway	C. Lillywhite	L. Castillo
2	17 October 2013	Final	S. McConway	S. McConway	C. Lillywhite	L. Castillo
<b>Current Revision</b>		2				

Approval					
Author Signature			Approver Signature		
Name	Steven McConway	Name	Luis Castillo		
Title	Structural Engineer	Title	Senior Structural Engineer		



# Contents

<b>Executive Summary</b>	<b>1</b>
<b>1 Introduction</b>	<b>2</b>
1.1 General	2
<b>2 Description of the Building</b>	<b>2</b>
2.1 Building Age and Configuration	2
2.2 Building Structural Systems Vertical and Horizontal	2
2.3 Reference Building Type	2
2.4 Building Foundation System and Soil Conditions	3
2.5 Available Structural Documentation and Inspection Priorities	3
2.6 Available Survey Information	3
<b>3 Structural Investigation</b>	<b>4</b>
3.1 Summary of Building Damage	4
3.2 Record of Intrusive Investigation	4
3.3 Damage Discussion	4
<b>4 Building Review Summary</b>	<b>4</b>
4.1 Building Review Statement	4
4.2 Critical Structural Weaknesses	4
<b>5 Building Strength (Refer to Appendix C for background information)</b>	<b>5</b>
5.1 General	5
5.2 Initial %NBS Assessment	5
5.3 Results Discussion	5
<b>6 Conclusions and Recommendations</b>	<b>6</b>
<b>7 Explanatory Statement</b>	<b>6</b>

# Appendices

**Appendix A Site Location, Photos and Levels Survey**

**Appendix B References**

**Appendix C Strength Assessment Explanation**

**Appendix D Background and Legal Framework**

**Appendix E Standard Reporting Spread Sheet**

# Executive Summary

This is a summary of the Qualitative Engineering Evaluation for the Spreydon Domain - Equipment Shed and Changing Room building and is based on the Detailed Engineering Evaluation Procedure document issued by the Engineering Advisory Group on 19 July 2011, visual inspections, available structural documentation and summary calculations as appropriate.

<b>Building Details</b>	<b>Name</b>	Spreydon Domain - Equipment Shed and Changing Room			
<b>Building Address</b>	33 Domain Terrace, Spreydon			<b>No. of residential units</b>	0
<b>Soil Technical Category</b>	N/A	<b>Importance Level</b>	2	<b>Approximate Year Built</b>	1982
<b>Foot Print (m<sup>2</sup>)</b>	85	<b>Storeys above ground</b>	1	<b>Storeys below ground</b>	0
<b>Type of Construction</b>	Light timber roof with steel sheeting and GIB ceiling, block-work walls, concrete strip footing with slab-on-grade.				

## Qualitative Results Summary

<b>Building Occupied</b>	Y	The Spreydon Domain - Equipment Shed and Changing Room is currently in use.
<b>Suitable for Continued Occupancy</b>	Y	The Spreydon Domain - Equipment Shed and Changing Room is suitable for continued occupation.
<b>Key Damage Summary</b>	Y	Refer to summary of building damage Section 3.1 of the report body.
<b>Critical Structural Weaknesses (CSW)</b>	N	No critical structural weaknesses were identified.
<b>Levels Survey Results</b>	Y	Variations in floor levels were outside the DBH's Guidelines, with falls of greater than 1:200 or 0.5% although this does not represent foundation damage as the falls are for drainage purposes.
<b>Building %NBS From Analysis</b>	51%	Based on an analysis of bracing capacity and demand.

## Qualitative Report Recommendations

<b>Geotechnical Survey Required</b>	N	Geotechnical survey not required due to lack of observed ground damage on site.
<b>Proceed to L5 Quantitative DEE</b>	N	A quantitative DEE is not required for this structure.

## Approval

<b>Author Signature</b>		<b>Approver Signature</b>	
<b>Name</b>	Steven McConway	<b>Name</b>	Luis Castillo
<b>Title</b>	Senior Structural Engineer	<b>Title</b>	Senior Structural Engineer

# 1 Introduction

## 1.1 General

On 23 August 2012 an Aurecon engineer visited the Spreydon Domain - Equipment Shed and Changing Room to carry out a qualitative building damage assessment on behalf of Christchurch City Council. Detailed visual inspections were carried out to assess the damage caused by the earthquakes on 4 September 2010, 22 February 2011, 13 June 2011, 23 December 2011 and related aftershocks.

The scope of work included:

- Assessment of the nature and extent of the building damage.
- Visual assessment of the building strength particularly with respect to safety of occupants if the building is currently occupied.
- Assessment of requirements for detailed engineering evaluation including geotechnical investigation, level survey and any areas where linings and floor coverings need removal to expose structural damage.

This report outlines the results of our Qualitative Assessment of damage to the Spreydon Domain - Equipment Shed and Changing Room and is based on the Detailed Engineering Evaluation Procedure document issued by the Structural Advisory Group on 19 July 2011, visual inspections, available structural documentation and summary calculations as appropriate.

## 2 Description of the Building

### 2.1 Building Age and Configuration


Built around 1982 the Spreydon Domain - Equipment Shed and Changing Room is a single storey building. The building has a light timber roof supporting corrugated metal roof sheeting and a GIB plasterboard ceiling. The concrete blockwork walls change around the building. They are unreinforced on the east side of the building and reinforced on the western side. This west side of the building, which was likely built after the east side as an extension, is reinforced with vertical reinforcing every 600mm. A bond beam is present throughout the structure. The building appears to have concrete strip footings and a slab-on-grade.

The approximate floor area of the building is 85 square metres. It is an importance level 2 structure in accordance with NZS 1170 Part 0:2002.

### 2.2 Building Structural Systems Vertical and Horizontal

The Spreydon Domain - Equipment Shed and Changing Room has a well-defined load path. Its light corrugated metal roof is supported on timber trusses that transfer loads to the block-work walls. The walls are supported on concrete strip footings. On the east side of the structure lateral loads are resisted by unreinforced block-work walls in each direction and on the west side of the structure lateral loads are resisted by reinforced block-work walls.

### 2.3 Reference Building Type



The Spreydon Domain - Equipment Shed and Changing Room is a basic structure typical of its age and style. We assume it was not subjected to specific engineering design; rather it was constructed to a reliable formula known to achieve the performance and aesthetic objectives of the time it was built.

## 2.4 Building Foundation System and Soil Conditions

The Spreydon Domain - Equipment Shed and Changing Room is assumed to have, as discussed above, concrete strip foundations and a slab-on-grade. The land and surrounds of Spreydon Domain - Equipment Shed and Changing Room are zoned N/A which means that no mapping of the land with respect to technical categories has been done. However, there are signs to the north Spreydon Domain - Equipment Shed and Changing Room of liquefaction bulges, boils or subsidence but this does not appear to extend past the road.

It is of note that adjacent land to the Spreydon Domain - Equipment Shed and Changing Room are zoned as Technical Category 2 (TC2) and minor to moderate land damage from liquefaction is possible in future earthquake events.

## 2.5 Available Structural Documentation and Inspection Priorities

No drawings were available for the Spreydon Domain - Equipment Shed and Changing Room. Inspection priorities related to a review of potential damage to foundations and consideration of wall bracing adequacy. The generic building type for the Spreydon Domain - Equipment Shed and Changing Room is 1980s unreinforced block-work structure. This type of structure has generally performed poorly during the Canterbury Earthquakes however it appears that the Spreydon Domain - Equipment Shed and Changing Room has performed better than expected.

## 2.6 Available Survey Information

A floor level survey was undertaken to establish the level of unevenness across the floors. The results of the survey are presented on the attached sketch in Appendix A. All of the levels were taken on top of the existing floor coverings which may have introduced some margin of error.

The Ministry of Business, Innovation and Employment (MBIE) published the guideline “Repairing and rebuilding houses affected by the Canterbury earthquakes” in 2012, which recommends some form of re-leveling or rebuilding of the floor

1. If the slope is greater than 0.5% for any two points more than 2m apart, or
2. If the variation in level over the floor plan is greater than 50mm, or
3. If there is significant cracking of the floor.

It is important to note that these figures are recommendations and are only intended to be applied to residential buildings. However, they provide useful guidance in determining acceptable floor level variations.

The floor levels for the Spreydon Domain - Equipment Shed and Changing Room were found to be outside the recommended tolerances, although the slopes would be required for drainage purposes and therefore do not represent foundation damage.



## 3 Structural Investigation

### 3.1 Summary of Building Damage

The Spreydon Domain - Equipment Shed and Changing Room is currently in use and was occupied at the time the damage assessment was carried out. The Spreydon Domain - Equipment Shed and Changing Room has performed well but has suffered minor damage to the floor and walls (see attached photographs). The floor has minor cracks running through it and the block-work wall has several minor cracks running along the mortar.

### 3.2 Record of Intrusive Investigation

Minor intrusive investigation was undertaken for the Spreydon Domain - Equipment Shed and Changing Room. The works consisted of using a scanner to look for steel. The investigation revealed that vertical reinforcement was present at 600mm centres on the west side of the structure and that a bond beam was present in all walls. No vertical reinforcing was found on the east side of the structure.

### 3.3 Damage Discussion

There was only minor damage observed to the Spreydon Domain - Equipment Shed and Changing Room which has been assumed to be the result of the recent seismic action.

## 4 Building Review Summary

### 4.1 Building Review Statement

As noted above minor intrusive investigations were carried out for the Spreydon Domain - Equipment Shed and Changing Room. Because of the generic nature of the building a significant amount of information can be inferred from an external and internal inspection.

### 4.2 Critical Structural Weaknesses

No specific critical structural weaknesses were identified as part of the building qualitative assessment. All damage appears to be minor and does not affect the structural strength of the building.

# 5 Building Strength (Refer to Appendix C for background information)

## 5.1 General

The Spreydon Domain - Equipment Shed and Changing Room is, as discussed above, a typical example of its generic style, 1980's structure built from concrete block-work walls. It is of a type of building that, due to its high weight and low bracing capacity, has typically performed poorly, however in this case it appears that the Spreydon Domain - Equipment Shed and Changing Room has performed well and there is only minor damage to the building related to the recent earthquakes.

## 5.2 Initial %NBS Assessment

It is assumed the Spreydon Domain - Equipment Shed and Changing Room has not been subject to specific engineering design and the initial evaluation procedure or IEP is not an appropriate method of assessment for this building. Nevertheless an estimate of lateral load capacity can be made by adopting assumed values for strengths of existing materials and calculating the capacity of existing walls.

Selected assessment seismic parameters are tabulated in the Table 1 on the next page.

Table 1: Parameters used in the Seismic Assessment

Seismic Parameter	Quantity	Comment/Reference
Site Soil Class	D	NZS 1170.5:2004, Clause 3.1.3, Deep or Soft Soil
Site Hazard Factor, Z	0.30	DBH Info Sheet on Seismicity Changes (Effective 19 May 2011)
Return period Factor, $R_u$	1.00	NZS 1170.5:2004, Table 3.5
Ductility Factor in Transverse Direction (Across), $\mu$	1.25	Combination of unreinforced and reinforced blockwork walls
Ductility Factor in Longitudinal Direction (Across), $\mu$	1.25	Combination of unreinforced and reinforced blockwork walls

The seismic demand for the Spreydon Domain - Equipment Shed and Changing Room has been calculated based on the current code requirements NZS4230:2004 and The University of Auckland "Assessment and Improvement of Unreinforced Masonry Buildings for Earthquake Resistance". The capacity of the existing walls in the building was calculated from assumed strengths of existing materials and the number and length of walls present for both the Along (east-west) and Across (north-south) directions. The seismic demand was then compared with the building capacity in these directions.

The building was found to have a sufficient number and length of walls in the Along direction. However in the Across direction the internal unreinforced masonry wall have a strength of 51% NBS. The walls were found to have an out of plane capacity of 57% NBS in both directions.

## 5.3 Results Discussion

This analysis shows that the Spreydon Domain - Equipment Shed and Changing Room has performed well in the recent earthquake events despite the construction type and strength. This would be most likely due to the small size of the building. Walls are also evenly distributed and this would therefore reduce the torsion imposed on the building from lateral loads.





## 6 Conclusions and Recommendations

As there is no clear evidence of any liquefaction or ground movement in the vicinity of the Spreydon Domain - Equipment Shed and Changing Room and as the results of the level survey did not reveal any settlements of concern, **a geotechnical investigation is currently not considered necessary.**

The building is currently occupied and in use and in our opinion the Spreydon Domain - Equipment Shed and Changing Room **is considered suitable for continued occupation.**

Cracking to the floor slab and concrete blockwork walls should be repaired by epoxy grout injection.

## 7 Explanatory Statement

The inspections of the building discussed in this report have been undertaken to assess structural earthquake damage. No analysis has been undertaken to assess the strength of the building or to determine whether or not it complies with the relevant building codes, except to the extent that Aurecon expressly indicates otherwise in the report. Aurecon has not made any assessment of structural stability or building safety in connection with future aftershocks or earthquakes – which have the potential to damage the building and to jeopardise the safety of those either inside or adjacent to the building, except to the extent that Aurecon expressly indicates otherwise in the report.

This report is necessarily limited by the restricted ability to carry out inspections due to potential structural instabilities/safety considerations, and the time available to carry out such inspections. The report does not address defects that are not reasonably discoverable on visual inspection, including defects in inaccessible places and latent defects. Where site inspections were made, they were restricted to external inspections and, where practicable, limited internal visual inspections.

To carry out the structural review, existing building drawings were obtained (where available) from the Christchurch City Council records. We have assumed that the building has been constructed in accordance with the drawings.

While this report may assist the client in assessing whether the building should be repaired, strengthened, or replaced that decision is the sole responsibility of the client.

This review has been prepared by Aurecon at the request of its client and is exclusively for the client's use. It is not possible to make a proper assessment of this review without a clear understanding of the terms of engagement under which it has been prepared, including the scope of the instructions and directions given to and the assumptions made by Aurecon. The report will not address issues which would need to be considered for another party if that party's particular circumstances, requirements and experience were known and, further, may make assumptions about matters of which a third party is not aware. No responsibility or liability to any third party is accepted for any loss or damage whatsoever arising out of the use of or reliance on this report by any third party.

Without limiting any of the above, Aurecon's liability, whether under the law of contract, tort, statute, equity or otherwise, is limited as set out in the terms of the engagement with the client.


# Appendices



# Appendix A

## Site Map, Photos and Levels Survey

23 August 2012 – Spreydon Domain - Equipment Shed and Changing Room Site Photographs

<p>Location of Spreydon Domain - Equipment Shed and Changing Room.</p>	
<p>Aerial photograph of Spreydon Domain - Equipment Shed and Changing Room.</p>	

Building southern elevation.




Building western elevation.




Crack in foundation slab.




Minor cracking to block-work.





TRUE NORTH



# FLOOR LEVELS PLAN

SCALE 1 : 100

S:\092012\11347.dwg



REV	DATE	REVISION DETAILS	APPROVAL
1	22-08-12	DEE SKETCH	LHOWARD

DRAWN	DESIGNED
D.LAKE	S.WALDRIP
CHECKED	
L.HOWARD	
APPROVED	
	DATE
L.HOWARD	

PROJECT
PAVILLION/TOILETS 33 DOMAIN TCE
TITLE
FLOOR LEVELS PLAN

AS BUILT
PROJECT No. 229618
SCALE 1 : 100
DRAWING No. S-01-00
SIZE A4
REV 1



# Appendix B

## References

1. The Ministry of Business, Innovation and Employment (MBIE) “Repairing and rebuilding houses affected by the Canterbury earthquakes”, 2012
2. New Zealand Society for Earthquake Engineering (NZSEE), “Assessment and Improvement of the Structural Performance of Buildings in Earthquakes”, April 2012
3. Standards New Zealand, “AS/NZS 1170 Part 0, Structural Design Actions: General Principles”, 2002
4. Standards New Zealand, “AS/NZS 1170 Part 1, Structural Design Actions: Permanent, imposed and other actions”, 2002
5. Standards New Zealand, “NZS 1170 Part 5, Structural Design Actions: Earthquake Actions – New Zealand”, 2004
6. Standards New Zealand, “NZS 3101 Part 1, The Design of Concrete Structures”, 2006
7. Standards New Zealand, “NZS 3404 Part 1, Steel Structures Standard”, 1997
8. Standards New Zealand, “NZS 3606, Timber Structures Standard”, 1993
9. Standards New Zealand, “NZS 3604, Timber Framed Structures”, 2011
10. Standards New Zealand, “NZS 4229, Concrete Masonry Buildings Not Requiring Specific Engineering Design”, 1999
11. Standards New Zealand, “NZS 4230, Design of Reinforced Concrete Masonry Structures”, 2004

# Appendix C

## Strength Assessment Explanation

### New Building Standard (NBS)

New building standard (NBS) is the term used with reference to the earthquake standard that would apply to a new building of similar type and use if the building was designed to meet the latest design Codes of Practice. If the strength of a building is less than this level, then its strength is expressed as a percentage of NBS.

### Earthquake Prone Buildings

A building can be considered to be earthquake prone if its strength is less than one third of the strength to which an equivalent new building would be designed, that is, less than 33%NBS (as defined by the New Zealand Building Act). If the building strength exceeds 33%NBS but is less than 67%NBS the building is considered at risk.

### Christchurch City Council Earthquake Prone Building Policy 2010

The Christchurch City Council (CCC) already had in place an Earthquake Prone Building Policy (EPB Policy) requiring all earthquake-prone buildings to be strengthened within a timeframe varying from 15 to 30 years. The level to which the buildings were required to be strengthened was 33%NBS.

As a result of the 4 September 2010 Canterbury earthquake the CCC raised the level that a building was required to be strengthened to from 33% to 67% NBS but qualified this as a target level and noted that the actual strengthening level for each building will be determined in conjunction with the owners on a building-by-building basis. Factors that will be taken into account by the Council in determining the strengthening level include the cost of strengthening, the use to which the building is put, the level of danger posed by the building, and the extent of damage and repair involved.

Irrespective of strengthening level, the threshold level that triggers a requirement to strengthen is 33%NBS.

As part of any building consent application fire and disabled access provisions will need to be assessed.

### Christchurch Seismicity

The level of seismicity within the current New Zealand loading code (AS/NZS 1170) is related to the seismic zone factor. The zone factor varies depending on the location of the building within NZ. Prior to the 22<sup>nd</sup> February 2011 earthquake the zone factor for Christchurch was 0.22. Following the earthquake the seismic zone factor (level of seismicity) in the Christchurch and surrounding areas has been increased to 0.3. This is a 36% increase.

For this assessment, the building's earthquake resistance is compared with the current New Zealand Building Code requirements for a new building constructed on the site. This is expressed as a percentage of new building standard (%NBS). The new building standard load requirements have been determined in accordance with the current earthquake loading standard (NZS 1170.5:2004 Structural design actions - Earthquake actions - New Zealand).

The likely capacity of this building has been derived in accordance with the New Zealand Society for Earthquake Engineering (NZSEE) guidelines 'Assessment and Improvement of the Structural Performance of Buildings in Earthquakes' (AISPBE), 2006. These guidelines provide an Initial Evaluation Procedure that assesses a buildings capacity based on a comparison of loading codes from when the building was designed



and currently. It is a quick high-level procedure that can be used when undertaking a Qualitative analysis of a building. The guidelines also provide guidance on calculating a modified Ultimate Limit State capacity of the building which is much more accurate and can be used when undertaking a qualitative analysis.

The New Zealand Society for Earthquake Engineering has proposed a way for classifying earthquake risk for existing buildings in terms of %NBS and this is shown in Figure C1 below.

Description	Grade	Risk	%NBS	Existing Building Structural Performance	Improvement of Structural Performance	
					Legal Requirement	NZSEE Recommendation
Low Risk Building	A or B	Low	Above 67	Acceptable (improvement may be desirable)	The Building Act sets no required level of structural improvement (unless change in use) This is for each TA to decide. Improvement is not limited to 34%NBS.	100%NBS desirable. Improvement should achieve at least 67%NBS
Moderate Risk Building	B or C	Moderate	34 to 66	Acceptable legally. Improvement recommended		Not recommended. Acceptable only in exceptional circumstances
High Risk Building	D or E	High	33 or lower	Unacceptable (Improvement	Unacceptable	Unacceptable

Figure C1: NZSEE Risk Classifications Extracted from table 2.2 of the NZSEE 2006 AISPBE Guidelines

Table C1 below compares the percentage NBS to the relative risk of the building failing in a seismic event with a 10% probability of exceedance in 50 years (i.e. 0.2% in the next year). It is noted that the current seismic risk in Christchurch results in a 6% probability of exceedance in the next year.

Table C1: Relative Risk of Building Failure In A

Percentage of New Building Standard (%NBS)	Relative Risk (Approximate)
>100	<1 time
80-100	1-2 times
67-80	2-5 times
33-67	5-10 times
20-33	10-25 times
<20	>25 times

# Appendix D

## Background and Legal Framework

### Background

This report is a Qualitative Assessment of the building structure, and is based on the Detailed Engineering Evaluation Procedure document (draft) issued by the Structural Advisory Group on 19 July 2011.

A qualitative assessment involves inspections of the building and a desktop review of existing structural and geotechnical information, including existing drawings and calculations, if available.

The purpose of the assessment is to determine the likely building performance and damage patterns, to identify any potential critical structural weaknesses or collapse hazards, and to make an initial assessment of the likely building strength in terms of percentage of new building standard (%NBS).

At the time of this report, no intrusive site investigation, detailed analysis, or modelling of the building structure had been carried out. Construction drawings were made available, and these have been considered in our evaluation of the building. The building description below is based on a review of the drawings and our visual inspections.

### Compliance

This section contains a brief summary of the requirements of the various statutes and authorities that control activities in relation to buildings in Christchurch at present.

### Canterbury Earthquake Recovery Authority (CERA)

CERA was established on 28 March 2011 to take control of the recovery of Christchurch using powers established by the Canterbury Earthquake Recovery Act enacted on 18 April 2011. This act gives the Chief Executive Officer of CERA wide powers in relation to building safety, demolition and repair. Two relevant sections are:

#### **Section 38 – Works**

This section outlines a process in which the chief executive can give notice that a building is to be demolished and if the owner does not carry out the demolition, the chief executive can commission the demolition and recover the costs from the owner or by placing a charge on the owners' land.

#### **Section 51 – Requiring Structural Survey**

This section enables the chief executive to require a building owner, insurer or mortgagee carry out a full structural survey before the building is re-occupied.

We understand that CERA will require a detailed engineering evaluation to be carried out for all buildings (other than those exempt from the Earthquake Prone Building definition in the Building Act). It is anticipated that CERA will adopt the Detailed Engineering Evaluation Procedure document (draft) issued by the Structural Advisory Group on 19 July 2011. This document sets out a methodology for both qualitative and quantitative assessments.

The qualitative assessment is a desk-top and site inspection assessment. It is based on a thorough visual inspection of the building coupled with a review of available documentation such as drawings and

specifications. The qualitative assessment involves analytical calculation of the buildings strength and may require non-destructive or destructive material testing, geotechnical testing and intrusive investigation.

It is anticipated that factors determining the extent of evaluation and strengthening level required will include:

- The importance level and occupancy of the building
- The placard status and amount of damage
- The age and structural type of the building
- Consideration of any critical structural weaknesses
- The extent of any earthquake damage

## Building Act

Several sections of the Building Act are relevant when considering structural requirements:

### Section 112 – Alterations

This section requires that an existing building complies with the relevant sections of the Building Code to at least the extent that it did prior to any alteration. This effectively means that a building cannot be weakened as a result of an alteration (including partial demolition).

### Section 115 – Change of Use

This section requires that the territorial authority (in this case Christchurch City Council (CCC)) be satisfied that the building with a new use complies with the relevant sections of the Building Code 'as near as is reasonably practicable'. Regarding seismic capacity 'as near as reasonably practicable' has previously been interpreted by CCC as achieving a minimum of 67%NBS however where practical achieving 100%NBS is desirable. The New Zealand Society for Earthquake Engineering (NZSEE) recommend a minimum of 67%NBS.

### Section 121 – Dangerous Buildings

The definition of dangerous building in the Act was extended by the Canterbury Earthquake (Building Act) Order 2010, and it now defines a building as dangerous if:

- in the ordinary course of events (excluding the occurrence of an earthquake), the building is likely to cause injury or death or damage to other property; or
- in the event of fire, injury or death to any persons in the building or on other property is likely because of fire hazard or the occupancy of the building; or
- there is a risk that the building could collapse or otherwise cause injury or death as a result of earthquake shaking that is less than a 'moderate earthquake' (refer to Section 122 below); or
- there is a risk that that other property could collapse or otherwise cause injury or death; or
- a territorial authority has not been able to undertake an inspection to determine whether the building is dangerous.

### Section 122 – Earthquake Prone Buildings

This section defines a building as earthquake prone if its ultimate capacity would be exceeded in a 'moderate earthquake' and it would be likely to collapse causing injury or death, or damage to other property. A moderate earthquake is defined by the building regulations as one that would generate ground shaking 33% of the shaking used to design an equivalent new building.

## Section 124 – Powers of Territorial Authorities

This section gives the territorial authority the power to require strengthening work within specified timeframes or to close and prevent occupancy to any building defined as dangerous or earthquake prone.

## Section 131 – Earthquake Prone Building Policy

This section requires the territorial authority to adopt a specific policy for earthquake prone, dangerous and insanitary buildings.

## Christchurch City Council Policy

Christchurch City Council adopted their Earthquake Prone, Dangerous and Insanitary Building Policy in 2006. This policy was amended immediately following the Darfield Earthquake of the 4th September 2010.

The 2010 amendment includes the following:

- A process for identifying, categorising and prioritising Earthquake Prone Buildings, commencing on 1 July 2012;
- A strengthening target level of 67% of a new building for buildings that are Earthquake Prone;
- A timeframe of 15-30 years for Earthquake Prone Buildings to be strengthened; and,
- Repair works for buildings damaged by earthquakes will be required to comply with the above.

The council has stated their willingness to consider retrofit proposals on a case by case basis, considering the economic impact of such a retrofit.

We anticipate that any building with a capacity of less than 33%NBS (including consideration of critical structural weaknesses) will need to be strengthened to a target of 67%NBS of new building standard as recommended by the Policy.

If strengthening works are undertaken, a building consent will be required. A requirement of the consent will require upgrade of the building to comply 'as near as is reasonably practicable' with:

- The accessibility requirements of the Building Code.
- The fire requirements of the Building Code. This is likely to require a fire report to be submitted with the building consent application.

## Building Code

The building code outlines performance standards for buildings and the Building Act requires that all new buildings comply with this code. Compliance Documents published by The Department of Building and Housing can be used to demonstrate compliance with the Building Code.

After the February Earthquake, on 19 May 2011, Compliance Document B1: Structure was amended to include increased seismic design requirements for Canterbury as follows:

- Hazard Factor increased from 0.22 to 0.3 (36% increase in the basic seismic design load)
- Serviceability Return Period Factor increased from 0.25 to 0.33 (80% increase in the serviceability design loads when combined with the Hazard Factor increase)

The increase in the above factors has resulted in a reduction in the level of compliance of an existing building relative to a new building despite the capacity of the existing building not changing.

# Appendix E

## Standard Reporting Spread Sheet

Detailed Engineering Evaluation Summary Data

V1.11

<b>Location</b>		Building Name: <u>Spreydon Domain - Equipment Shed &amp; Changing Room</u>	Reviewer: <u>Lee Howard</u>
Building Address: <u>Unit No: Street</u>	33 Domain Tce	CP/Eng No: <u>1008889</u>	Company: <u>Aurecon</u>
Legal Description: <u>RES 3824</u>		Company project number: <u>229618</u>	Company phone number: <u>03 375 0761</u>
GPS south: <u>43</u>	Degrees <u>33</u> Min <u>22</u> Sec <u>34</u>	Date of submission: <u>17/10/2013</u>	Inspection Date: <u>23/08/2012</u>
GPS east: <u>172</u>	<u>36</u> <u>8</u> <u>11</u>	Revision: <u>2</u>	Is there a full report with this summary? <u>yes</u>
Building Unique Identifier (CCC): <u>FRK 1099 BLDG_008</u>	5205		

<b>Site</b>	Site slope: <u>flat</u>	Max retaining height (m): <u></u>
	Soil type: <u>mixed</u>	Soil Profile (if available): <u></u>
	Site Class (to NZS1170.5): <u>D</u>	If Ground improvement on site, describe: <u></u>
Proximity to waterway (m, if <100m): <u></u>		Approx site elevation (m): <u>12.00</u>
Proximity to cliff top (m, if <100m): <u></u>		
Proximity to cliff base (m, if <100m): <u></u>		

<b>Building</b>	No. of storeys above ground: <u>1</u>	single storey = 1	Ground floor elevation (Absolute) (m): <u>12.20</u>
	Ground floor split? <u>no</u>		Ground floor elevation above ground (m): <u>0.20</u>
	Storeys below ground: <u>0</u>		
	Foundation type: <u>strip footings</u>		if Foundation type is other, describe: <u></u>
	Building height (m): <u>2.40</u>	height from ground to level of uppermost seismic mass (for IEP only) (m): <u></u>	Date of design: <u>1976-1992</u>
	Floor footprint area (approx): <u>85</u>		
	Age of Building (years): <u>30</u>		
	Strengthening present? <u>no</u>		If so, when (year)? <u></u>
	Use (ground floor): <u>other (specify)</u>		And what load level (%g)? <u></u>
	Use (upper floors): <u></u>		Brief strengthening description: <u></u>
	Use notes (if required): <u>Change rooms and toilet</u>		
	Importance level (to NZS1170.5): <u>IL2</u>		

<b>Gravity Structure</b>	Gravity System: <u>load bearing walls</u>	rafter type, purlin type and cladding: <u></u>
	Roof: <u>timber framed</u>	slab thickness (mm): <u></u>
	Floors: <u>concrete flat slab</u>	overall depth x width (mm x mm): <u></u>
	Beams: <u>none</u>	thickness (mm): <u>190</u>
	Columns: <u></u>	
	Walls: <u>partially filled concrete masonry</u>	

<b>Lateral load resisting structure</b>	Lateral system along: <u>unreinforced masonry bearing wall - brick</u>	<b>Note: Define along and across in detailed report!</b>	
	Ductility assumed, μ: <u>1.25</u>	0.40 from parameters in sheet	note wall thickness and cavity estimate or calculation? <u>estimated</u>
	Period along: <u>0.40</u>		estimate or calculation? <u>estimated</u>
	Total deflection (ULS) (mm): <u>0</u>		estimate or calculation? <u>estimated</u>
	maximum interstorey deflection (ULS) (mm): <u>0</u>		
	Lateral system across: <u>unreinforced masonry bearing wall - brick</u>	0.00	note wall thickness and cavity estimate or calculation? <u>estimated</u>
	Ductility assumed, μ: <u>1.25</u>		estimate or calculation? <u>estimated</u>
	Period across: <u>0.40</u>		estimate or calculation? <u>estimated</u>
	Total deflection (ULS) (mm): <u>0</u>		estimate or calculation? <u>estimated</u>
	maximum interstorey deflection (ULS) (mm): <u>0</u>		

<b>Separations:</b>	north (mm): <u></u>	leave blank if not relevant
	east (mm): <u></u>	
	south (mm): <u></u>	
	west (mm): <u></u>	

<b>Non-structural elements</b>	Stairs: <u>exposed structure</u>	describe: <u></u>
	Wall cladding: <u>metal</u>	describe: <u></u>
	Roof Cladding: <u>metal</u>	
	Glazing: <u></u>	
	Ceilings: <u>plaster, fixed</u>	
	Services (list): <u></u>	

<b>Available documentation</b>	Architectural: <u>none</u>	original designer name/date: <u></u>
	Structural: <u>none</u>	original designer name/date: <u></u>
	Mechanical: <u>none</u>	original designer name/date: <u></u>
	Electrical: <u>none</u>	original designer name/date: <u></u>
	Geotech report: <u>none</u>	original designer name/date: <u></u>

<b>Damage</b>	Site performance: <u>good</u>	Describe damage: <u></u>
Site: (refer DEE Table 4-2)	Settlement: <u>none observed</u>	notes (if applicable): <u></u>
	Differential settlement: <u>none observed</u>	notes (if applicable): <u></u>
	Liquefaction: <u>none apparent</u>	notes (if applicable): <u></u>
	Lateral Spread: <u>none apparent</u>	notes (if applicable): <u></u>
	Differential lateral spread: <u>none apparent</u>	notes (if applicable): <u></u>
	Ground cracks: <u>none apparent</u>	notes (if applicable): <u></u>
	Damage to area: <u>none apparent</u>	notes (if applicable): <u></u>

<b>Building:</b>	Current Placard Status: <u></u>	
Along	Damage ratio: <u>0%</u>	Describe how damage ratio arrived at: <u></u>
	Describe (summary): <u></u>	
Across	Damage ratio: <u>0%</u>	$Damage\_Ratio = \frac{(\%NBS\ (before) - \%NBS\ (after))}{\%NBS\ (before)}$
	Describe (summary): <u></u>	
Diaphragms	Damage?: <u>no</u>	Describe: <u></u>
CSWs:	Damage?: <u>no</u>	Describe: <u></u>
Pounding:	Damage?: <u>no</u>	Describe: <u></u>
Non-structural:	Damage?: <u>no</u>	Describe: <u></u>

<b>Recommendations</b>	Level of repair/strengthening required: <u>none</u>	Describe: <u></u>
	Building Consent required: <u>no</u>	Describe: <u></u>
	Interim occupancy recommendations: <u>full occupancy</u>	Describe: <u></u>
Along	Assessed %NBS before e'quakes: <u>57%</u> ##### %NBS from IEP below	If IEP not used, please detail assessment methodology: <u>Analysis of Capacity and Demand</u>
	Assessed %NBS after e'quakes: <u>57%</u>	
Across	Assessed %NBS before e'quakes: <u>51%</u> ##### %NBS from IEP below	
	Assessed %NBS after e'quakes: <u>51%</u>	

<b>IEP</b>	Use of this method is not mandatory - more detailed analysis may give a different answer, which would take precedence. Do not fill in fields if not using IEP.	
Period of design of building (from above): <u>1976-1992</u>		h <sub>n</sub> from above: <u>m</u>
Seismic Zone, if designed between 1965 and 1992: <u></u>		not required for this age of building not required for this age of building
	Period (from above): <u>0.4</u>	along <u>0.4</u> across <u>0.4</u>
	(%NBS) <sub>nom</sub> from Fig 3.3: <u></u>	
Note:1 for specifically design public buildings, to the code of the day: pre-1965 = 1.25; 1965-1976, Zone A = 1.33; 1965-1976, Zone B = 1.2; all else 1.0		
Note 2: for RC buildings designed between 1976-1984, use 1.2		
Note 3: for buildings designed prior to 1935 use 0.8, except in Wellington (1.0)		
	along <u>0%</u> across <u>0%</u>	
	Final (%NBS) <sub>nom</sub> : <u>0%</u>	

2.2 Near Fault Scaling Factor

Near Fault scaling factor, from NZS1170.5, cl 3.1.6:

Near Fault scaling factor (1/N(T,D), Factor A:  along  across  
#DIV/0! #DIV/0!

2.3 Hazard Scaling Factor

Hazard factor Z for site from AS1170.5, Table 3.3:   
Z<sub>1992</sub>, from NZS4203:1992   
Hazard scaling factor, Factor B:  #DIV/0!

2.4 Return Period Scaling Factor

Building Importance level (from above):  2  
Return Period Scaling factor from Table 3.1, Factor C:

2.5 Ductility Scaling Factor

Assessed ductility (less than max in Table 3.2)  along  across  
Ductility scaling factor: =1 from 1976 onwards; or =k<sub>μ</sub>, if pre-1976, from Table 3.3:

Ductility Scaling Factor, Factor D:  1.00  1.00

2.6 Structural Performance Scaling Factor:

Sp:   
Structural Performance Scaling Factor Factor E:  #DIV/0!  #DIV/0!

2.7 Baseline %NBS, (NBS%)<sub>0</sub> = (%NBS)<sub>nom</sub> x A x B x C x D x E

%NBS<sub>0</sub>:  #DIV/0!  #DIV/0!

Global Critical Structural Weaknesses: (refer to NZSEE IEP Table 3.4)

3.1. Plan Irregularity, factor A:  1

3.2. Vertical irregularity, Factor B:  1

3.3. Short columns, Factor C:  1

3.4. Pounding potential Pounding effect D1, from Table to right   
Height Difference effect D2, from Table to right   
Therefore, Factor D:  0

3.5. Site Characteristics  1

3.6. Other factors, Factor F

For ≤ 3 storeys, max value =2.5, otherwise max value =1.5, no minimum  Along  Across  
Rationale for choice of F factor, if not 1

Detail Critical Structural Weaknesses: (refer to DEE Procedure section 6)

List any:  Refer also section 6.3.1 of DEE for discussion of F factor modification for other critical structural weaknesses

3.7. Overall Performance Achievement ratio (PAR)  0.00  0.00

4.3 PAR x (%NBS)<sub>0</sub>: PAR x Baseline %NBS:  #DIV/0!  #DIV/0!

4.4 Percentage New Building Standard (%NBS), (before)  #DIV/0!

Official Use only:

Accepted By:   
Date:



**Aurecon New Zealand Limited**

**Level 2, 518 Colombo Street  
Christchurch 8011**

PO Box 1061  
Christchurch 8140  
New Zealand

**T** +64 3 375 0761

**F** +64 3 379 6955

**E** [christchurch@aurecongroup.com](mailto:christchurch@aurecongroup.com)

**W** [aurecongroup.com](http://aurecongroup.com)

Aurecon offices are located in:

Angola, Australia, Botswana, China,  
Ethiopia, Hong Kong, Indonesia,  
Lesotho, Libya, Malawi, Mozambique,  
Namibia, New Zealand, Nigeria,  
Philippines, Singapore, South Africa,  
Swaziland, Tanzania, Thailand, Uganda,  
United Arab Emirates, Vietnam.