

INDICATIVE LANDSCAPE PLAN FINAL

8-9-١Eo 0

100

50

PERIMETER OF PARK

If and when the field layout is reconfigured, investigate the feasibility and desirability of constructing a pathway of either asphalt or compacted grit around the perimeter of the soccer fields. The renewal of the drain and swale should be considered as part of this investigation. An asphalt pathway shall be constructed around the remaining perimeter and central area of the park to improve all weather access to the greater park and to link in with the existing path network.

Proposed post and cable barrier along the Memorial Avenue frontage with bollards at the sealed entrance way.

TOILETS

Upgrade the existing public toilet. Clearly define and limit the hours of use which should include closure during the hours of darkness.

Improve signage and the visibility of the toilet block adjacent to the Rugby Club.

(9) Proposed location for a new toilet block in the future.

WOODED AREA

Existing children's playground (including slide, swings and see-saw). Assess the use and safety of playground when due for renewal.

Attach name plates to all 38 notable trees.

Proposed trial location for a Frisbee-Golf course in the wooded area and the area between the tennis courts and Memorial Avenue.

CENTRAL AREA

The existing car park. Recommend that the layout of the car park is modified to include a larger number of car parks and a general enhancement including post and cable barriers and low amenity planting. The car park will require further investigation and detailed design including consideration of speed humps and a one-way system.

The existing pump house is to be retained (still in use). The exterior is to be enhanced including painting.

The existing water tower is to be demolished by telecommunication companies if and when no longer required for telecommunication purposes as per current licence

Investigate the former use of foundations and existence of a driveway to the former Boag homestead. Retain and interpret accordingly.

Existing Waimairi Stream margins are to be enhanced with low stream-side planting. This will create a cohesive network through the park and maintain key sightlines from car parking areas to club facilities and sports fields. Also investigate stream flow augmentation

Proposed new footbridge over Waimairi Stream.

Existing access over Waimairi Stream to be enhanced.

Existing Waimairi Stream headwall to be enhanced.

In order to reduce concealment (crime prevention) possiblities and to tidy the area, S occer and Cricket clubs shall be actively encouraged to store all equipment within the main clubroom building and to remove the pre-fab shed. In the interim, a secure fenced area shall be created on the north-west side of the pre-fab for all equipment not stored within the main clubroom building or the pre-fab.

The existing informal BMX area behind the Bowling Club shall be contained to prevent its spread and monitored to enable an assessment of its impact on this area of the park and its users.

Remove the former council nursery house and garage.

Replace the wire mesh fence on Avonhead Road adjacent to the playground with a pool style fence, replace the brick wall adjacent to the Bowling Club with a post and cable barrier

The existing children's Playground. Recommend the upgrade of the playground when up for renewal to include a wider range of equipment as well as additional seating and BBQ facilities. Ensure appropriate shelter is provided.

Proposed future full sized basketball court to be an extension of the children's playground.

LIGHTING

Investigate the existing lighting within and around the park, particularly around high use areas such as buildings, car parks and footpaths. Where required upgrade lights and investigate the possibility of additional lighting along proposed footpaths. Ensure all lighting is consistent in terms of design and illumination levels and conforms to current lighting standards. No other areas should be lit unless a future CPTED recommendation is made to the contrary.



LP336301 - L02 / 4 CP500328